

کوٹیشن فارم

APS (Boys) SRR

1. Construction of Guard Room / Washroom at Main Gate.
2. Replacement of 5 x Old Doors of Class Room.
3. Purchase of 6 x Window Roller Blinds for Pre I Class.
4. Purchase of 1 x Grass Cutter Machine (Tractor).
5. Replacement of 5 x Broken Tubewell Supply Valve (Plastic) With Iron Valve 4".
6. Replacement of Washroom Door.

نام فرم:

ایڈریس:

رابطہ نمبر:

شرائط و ضوابط

- ۱۔ کوٹ کردہ ریٹ میں تمام طرح کے ٹیکس شامل تصور ہوں گے۔ ہر آئٹم کا ریٹ علیحدہ سے دیں۔
- ۲۔ کمپنی سکوپ آف ورک کے مطابق کام کرنے کی پابند ہوگی جو کہ ساتھ لف ہے۔ تمام کام پراجیکٹ آفیسر کی نگرانی میں ہوں گے۔ صرف منظور شدہ سامان ہی تعمیر میں استعمال ہو گا۔ منظور شدہ سامان کی لسٹ لاگ برانچ (پروجیکٹ سیل) سے حاصل کی جاسکتی ہے۔ ناقص، غیر معیاری اور اور غیر تصدیق شدہ سامان استعمال کرنے کی اجازت نہیں ہوگی۔ جس کی بنیاد پر ٹھیکہ منسوخ کیا جاسکتا ہے۔
- ۳۔ پروجیکٹ کاسٹ کا ہیمنٹ شیڈول بنے گا۔ چیک کمپنی کے نام پر ایشو کیا جائے گا۔
- ۴۔ پروجیکٹ کے بارے میں اگر کوئی شکوک و شبہات ہوں تو پہلے سے کلئیر کر لئے جائیں۔ بعد میں LGES اس کا ذمہ دار نہ ہوگا۔
- ۵۔ 5% سکیورٹی ہر بل میں سے کاٹ لی جائے گی۔ جو گارنٹی پیریڈ پورا ہونے کے بعد ملے گی۔ مکمل ہیمنٹ User Certificate کے بعد دی جائے گی۔
- ۶۔ 3% تک ایکسٹروک اور کام کی بلا معاوضہ گنجائش ہوگی۔
- ۷۔ پروجیکٹ کے ابتداء اور آخر میں سائیٹ کلئیرینس کنٹریکٹر کی ذمہ داری ہوگی۔
- ۸۔ حاکم مجازیہ حق محفوظ رکھتے ہیں کہ کسی ایک یا تمام پیشکشوں کو وجہ بتائے بغیر قبول / مسترد کر دیں۔
- ۹۔ کوٹیشن مورخہ ۹ فروری 2026 تک بذریعہ ای میل بھیجی جاسکتی ہے۔ ای میل ایڈرس نیچے دیا گیا ہے۔

Email:

To: dydirprojs@lges.edu.pk

CC: ddlog@lges.edu.pk


لیفٹیننٹ کرنل (ریٹائرڈ)

NOTICE
CONSTRUCTION OF GUARD ROOM ALONGWITH WASHROOM
APS (B) SRR

Ser	Details	Unit	Qty	Rate	Amount
<u>Guard Room Size : 12' x 15'</u>					
1.	Excavation depth 2' x 1.5' & ground level upto 1' at DPC level	Cft	165		
2.	Laying of Brick blast (4" thick) fully compacted and PCC work (1:3:6) thick 4"	Job-1			
3.	Laying of DPC (thickness 2") and 2 x cot ultra chemical for water proofing	Job-1			
4.	Brick work with CS mortar (1:5) Bricks (best quality)	Cft	661		
5.	Providing and installation of fiber doors with fiber frame (3.5' x 7')	No	2		
6.	Installation of aluminum window (1.6mm Chawla / GR) window size 5' x 4') with fly net, marble sills, safety grill and window shade (6' x 3' x 3")	Sqft	40		
7.	Instl of 2 x window blinds (best quality) window size 6' x 5'	Sqft	42		
8.	Construction of RCC Beam at window and doors (height 9", 1 foot overlap on both sides	Job-1			
9.	Laying of Roof slab (covered area 16' x 19'), thick 6", steel 4sooter, square size 6" x 7". Steel brands (Mughal, SJ & Kamran)	Job-1			
10.	Installation of 8 x ceiling lights (7 Watts SMD Philips) and 1 x ceiling fan (56" Royal / GFC) with complete fittings / wirings, switch boards / sheet completed in all respect.	Job-1			
11.	Plaster work (inner side completed	Sqft	648		
12.	Mud filling with compaction and brick blast 4" fully compacted and PCC 3" (1:3:6)	Job			
13.	Roof treatment (2 x coats of ultra chemical, laying of polythene sheet best quality, mud filling 3", brick tile with mortar (1:4) and grouting)	Job-1			
14.	Laying of floor tiles (2'x2') and skirting (6") around the room. Tile AAA grade Master, Orient, Oriel & Times	Sqft	152		
15.	Providing and fixing of Gutka (best quality) outer side (4 x sides of room)	Job-1			
16.	Construction of parapet wall 4.5", height 3' and plaster work both side and fixing drain pipe PVC 3" (popular). (completed in all respect)	Job-1			
17.	Construction of steps as per site requirement (completed in all respect)	Job-1			
<u>Const Washroom Size : 6' x 4'</u>					
1.	Excavation depth 1' x 1' & ground level upto 1' at DPC level	Cft	22		
2.	Laying of Brick blast (3" thick) fully compacted and PCC work 4" thick (1:3:6)	Job-1			
3.	Laying of DPC (thickness 2") and 2 x cot ultra chemical for water proofing	Job-1			
4.	Brick work (2' x 9", 10' x 4.5") with CS mortar (1:5)	Cft	102		
5.	Providing and installation of fiber doors with fiber frame (2.5' x 7')	No	1		
6.	Installation of exhaust fan 12" plastic body (Royal/GFC)	No	1		
7.	Laying of Roof slab (covered area 7' x 9'), thick 5", steel 4sooter, square size 6" x 7". Steel brands (Mughal, SJ & Kamran)	Job-1			
8.	Installation of 2 x ceiling lights (7 Watts SMD Philips) with complete fittings / wirings, switch boards / sheet completed in all respect	Job-1			
9.	Plaster work (inner side completed	Sqft	200		
18.	Mud filling with compaction and brick blast 4" fully compacted and PCC 3" (1:3:6)	Job			
10.	Roof treatment (2 x coats of ultra chemical, laying of polythene sheet best quality, mud filling 3", brick tile with mortar (1:4) and grouting)	Job-1			
11.	Laying of tiles (1'x1.5') at floor and around the walls upto 4'. Tile AAA grade Master, Orient, Oriel & Times	Sqft	104		
12.	Providing and fixing of Gutka (best quality) outer side (4 x sides of wash room)	Job-1			
13.	Provision of water tank 250 Gln (Master / Dura) and Laying of water connection (under ground pipes (PPRC 32mm / 25mm) Popular	Job-1			
14.	Providing and fixing of 1 x wash basin and 1 x WC (Indian type) with flush tank (Durr) alongwith allied accessory (i.e pillar cock, T cock, D/bibcock, Muslim shower & connection pipe. Provision of soap dish and towel stand etc	Job-1			
15.	Installation of looking mirror 6mm (2'x2') with complete fittings and fixtures	Job-1			
16.	Laying of Sewerage line PVC pipe (4") Popular connecting with main sewerage line	Job-1			
19.	Construction of steps as per site requirement (completed in all respect)	Job-1			
Total					

REPLACEMENT OF 5 X OLD CLS ROOM DOORS

APS (BOYS) SRR

Ser	Work	A/U	Qty	Rate	Amount
1.	Replacement of 5 x old cls room doors 3.5' x 7'	Nos	5		
Total					

PURCHASE OF 6 X WINDOW ROLLER BLINDS FOR PRE-I CLASSES

APS (BOYS) SRR

Ser	Work	A/U	Qty	Rate	Amount
1.	Purchase of 6 x Window roller blinds 8' x 8'	Nos	6		
Total					

PURCHASE OF 1 X GRASS CUTTER MACHINE (TRACTOR)

APS (BOYS) SRR

Ser	Work	A/U	Qty	Rate	Amount
1.	Purchase of 1 x Grass Cutter Machine (Tractor)	Nos	1		
Total					

**REPLACEMENT OF 5 X BROKEN TUBE WELL SUPPLY VALVES
(PLASTIC) WITH IRON VALVES**

APS (BOYS) SRR

Ser	Work	A/U	Qty	Rate	Amount
1.	Replacement of 5 x Broken tube well supply valves 4" (plastic) with iron valves 4"	Nos	5		
Total					

REPLACEMENT OF WASHROOM DOOR

APS (BOYS) SRR JNR WING

Ser	Work	A/U	Qty	Rate	Amount
1.	Replacement of 1 x Door of washroom 2.5' x 7'	Nos	1		
2.	Replacement of 1 x double wire Gauze door of	"	1		